

APPROVAL CERTIFICATE

M63077/21/MN/mn IT FILE 21.IT.3989562.138

Page 1/1

TYPE APPROVAL CERTIFICATE

1. General:

Name and address of the factory: FIERRE S.r.l. – Via Vigentina 110B – 27100 - Pavia Type(s) of product and component manufactured: FI-HEG HIGH EXP. FOAM GENERATOR Type Tests witnessed on July 26, 2021 by M. Nicoletti

2. Type description:

- High Expansion Foam Generator Model FI-HEG
- EN13565
- GPL Fire

3. Conclusion:

After examination of the following documents:

- test reports for type approval n° M63076/21/MN/mn dated 26/07/2021

the undersigned, Inspector to Bureau Veritas, certifies that the above type meets the applicable requirements

This entire approval cycle remains valid as long as no significant changes are made to the audited facility, its production rate and its quality system. These conditions shall be assessed and certified once per year by means of a Factory Approval Audit.

This approval is an integral and indissociable part of the certification process managed by Bureau Veritas as defined in BV procedure GM SI 210.

Attachments:

- all the examined documents with BV "Reviewed" stamp,
- BV Report M63076/21/MN/mn

Inspected by: Name: M. Nicoletti

Signature..

Name: D. Morandin

Checked by:

Signature...

Date of issue: July 26, 2021

Expiring date: July 25, 2024

Inspection centre: BV Milan



Document No.: M63076/21/MN/mn IT FILE 21.IT.3989562.138

Page 1/2

TEST REPORT FOR TYPE APPROVAL

1. General:

Name and address of the factory: FIERRE Srl – Via Vigentina 110B – 27100 - Pavia Type(s) of product and component manufactured: FI-HEG HIGH EXP. FOAM GENERATOR Factory Audit Report: ISO 9000 Certificate no. 11777/04/S issued by RINA Exp. 2019-10-12 Type Tests witnessed on July 26, 2021 by M. Nicoletti

2. List of examined documents:

- o General Arrangement Dwg. FI-HEG 4
- o High expansion foam test procedure No. 26072021
- o EN13565

3. Observations and results:

o test conditions:

Pressure 4-6 bar;

Sabofoam Plurex M 3% synthetic foam

GPL Fire

Air temperature: 80°C +/- 10

o Test Report No.: FI-HEG4-2021

4. Conclusion:

At the request of the above manufacturer, made by its application dated March 25, 2019 and within the general conditions of service of Bureau Veritas and the applicable requirements of BV procedures, the above type test was performed and the results were found satisfactory.



Document No.: M63076/21/MN/mn IT FILE 21.IT.3989562.138

Page 2/2

TEST REPORT FOR TYPE APPROVAL

Attachments:

- Test Report No.: FI-HEG4-2021

Inspected by:	Checked by:
Name: M. Nicoletti Signature	Name: D. Morandin Signature.
Date of issue: July 26, 2021	Series Hours
Inspection centre: BV Milan	VERITO
Distribution: CLIENT MANUFAC	TURER






E-Mail info@fierre.com info@pec.fierre.com Sito Web www.fierre.com

Test Report No.: FI-HEG4-2021

TESTING PROCEDURES AND REPORTS HIGH EXPANSION FOAM GENERATOR Mod. FI-HEG 4

Test witnessed by Bureau Veritas Inspector Certificate n° M63077/21/MN/mn





REV.	DESCRIPTION	DATE	EDITED	VERIFIED	APPROVED
0	ISSUED	26-07-21	M.R.	M.R.	F.R.





E-Mail info@fierre.com info@pec.fierre.com Sito Web www.fierre.com

Test Report No.: FI-HEG4-2021

Introduction

This manual has been produced to test the correct operation of the high expansion foam generator model FI-HEG 4.

The test has been specifically carried out in an oversized area compared to the minimum size required by current standards, in order to simulate the actual conditions of a real installation, especially by taking into account a foam drop of 9 mt high in order to assess the real impact of the extinguishing agent on the ground.

Test carried out in a Fire House of the following dimensions:

Area 6.65 x 7.55 Mt.

Height 9.990 Mt.

Height of installation 9.0 Mt.

The test has been carried out in compliance with the parameters of standards EN 13565-2, taking into account the volume to be saturated, including the multiplication factors CN and CL.

1 Hydraulic and Mechanical Tests

In compliance with standards EN 13565-1 ENCLOSURE "A" EN 13565 4.3.1, a hydrostatic tightness test at 16 bar for 60' has been carried out, followed by a mechanical tightness test at 36 bar for 1'. The test has been successfully carried out on the manifold.





E-Mail info@fierre.com info@pec.fierre.com Sito Web www.fierre.com

Test Report No.: FI-HEG4-2021

2 Functional Tests

The first test carried out with water only has specified the foam generator flow rate. With the second test carried out with foam, we have specified the equipment performance. The test has been carried out with hot and polluted air generated by GPL combustion.

Foam production, its correct mixing and the supply pressure have been tested with the following equipment:

- ✓ transit time flowmeter MANUFACTURER: BIEMME TECNOLOGIE INDUSTRIALI MOD: TTFM100B-HH-NG - SERIAL NO.: 2018000011922
- ✓ Pressure meter MANUFACTURER: GEFRAN MOD: TK-E-1-M-B03D-M-V TYPE: 2130X000X00
- ✓ Data recording PLC: MANUFACTURER: JUMO LOGOSCREEM nt MOD: B 706581.1

The test have been carried out by continually recording the flow rate and pressure values by using TV cameras located inside different parts of the rooms. The video recordings have not been included in this report but can be viewed in Fierre S.r.l. offices.

3 Test Result

Flow rate test:

Pressure (bar)	Flow rate (lpm)	K (lpm@1bar)
5,3	415	180,26





Registered Office and Administration: Via Vigentina 110/B – 27100 Pavia (PV) VAT No. 01693540187 – Registered in Pavia company register under no. 1693540187

Tel +39 0382 957124 +39 0382 957125 Fax +39 0382 957126
E-Mail <u>info@fierre.com</u> info@pec.fierre.com Sito Web www.fierre.com

Test Report No.: FI-HEG4-2021

Foam expansion test:

Mixing ratio 3%

Fire fighting foam used Sabofoam Plurex M

Burned substance GPL

Local area 50,2 m²

Analysed test duration t=60"

Pressure at the equipment 5,3 bar (records and chart file enclosed)

Height of foam achieved 4,12 mt.

EN 13565 coefficients CN 1,15

CL 1,2

Volume produced 285,52 Mc

Generator flow rate 415 lpm

Expansion ratio 1:688


4 Conclusion

In date 26-07-2021, thanks to the presence of Bureau Veritas Inspector as witnessed Notified Body, we declare that the high expansion foam generator mod. FI-HEG 4 with a flow rate of 415 lt/min at 5,3 bar, performed an expansion ratio of 1:688 aspirating hot and polluted air generated by GPL combustion. Used foam concentrate has been Sabofoam Plurex M mixed at a 3%.

The above data has been obtained by applying standards EN 13565-1 and 13565-2

5 Enclosures

- ✓ Continuous pressure reading (the discharge seconds are shown in green)
- ✓ Pressure chart
- ✓ System sketch



ø935 Max ø925

CARATTERISTICHE TECNICHE

lechnical characteristic

Body : Stainless Steel CORPO : ACCIAIO INOX

CONO EROGATORE : ACCIAIO INOX

SUPPORTI : ACCIAIO INOX Delivery cone : Stainless Steel

Supports : Stainless Steel

COLLETTORE ALIMENTAZIONE : ACCIAIO AL CARBONIO

Feeding Reiser : Carbon Steel

Nozzles : Brass - (N*12 HEG-4)

CONNESSIONE : FLANGIA PN16 / FILETTATURA Gas / RULLATURA Ø76

UGELLI : OTTONE - (Nº12 HEG-4)

Connection : Flange PN16 / Threaded Gas / Grooved ø76

Theoretic total weight : 60 Kg. PESO TOTALE TEORICO : 60 Kg.

Painting, only feeding reiser: Red RAL 3000 Thk.=>100 Micron VERNICIATURA SOLO CROCERA PORTA UGELLI : ROSSO RAL 3000 Sp.=>100 Micron

Il presente disegno è di proprietà FERRE E' VIEIATO riprodurto e folisticario. / This drawing is the property of FERRE il CAN'T BE reproduced without our written approvai CARPENIERM/CLAPPENIRY | FIND A/UP 10 1000 ± 1 OLITE/OVER ± 1.5 x METRO | ANCOLL/ANGLES | FIND A/UP 10 6 ±1" > 6 € 30 ± 10" > 30 € 120 ± 20" OLITE/OVER 30"

ROSSO - 0.5 GMLLO - 0.18 VERDE - 0.35 CMNO - 0.7 BLU - 0.13 MAGENTA - 0.25 BMNCO - 0.25 8 - 0.09

LAVORAZIONI MECCANICHE FINO A/UP TO 315 > 315 € 1000 > 1000 € 2000

0.5

ANSI GASKET SURFACE FINISHES 125+250 AARH

QUANTITA' RICHIESTA : N' Required quantity : N

piece

PEZZ

540 -470

N°4 Ø11

465

935 Max

PORTATA/DELIVERY : (415 Lt./min @ 5.3 Bar HEG-4)

